

10CV65

## Sixth Semester B.E. Degree Examination, Dec.2017/Jan 2018 Hydraulic Structures and Irrigation Design Drawing

Time: 4 hrs.

Max. Marks: 100

Note: 1. Answer any FWO full questions form PART A and ONE question from PART B

- 2. Draw neat diagram wherever necessary
- 3. Missing data may suitably be assumed.

## PART-A

a. Define: i) Yield, ii) Trap efficiency iii) Density currents.

(03 Marks)

b. The construction cost for certain possible heights of dam at a given site have been estimated and are given in table, along with storage capacity at these heights. Determine the most economical height of dam:

Height (m)	10	20	30	40	50	60	65
Construction cost (million Rs.)	40	8	12	18	27	39	50
Storage (million cum)	50	110	180	250	350	500	600

(05 Marks)

Explain briefly environmental effects of construction of a reservoir.

(07 Marks)

What are the modes of failure of gravity dam? Explain. 2

(07 Marks)

b. Design the practical profile of a gravity dam of stone masonry, given the following data:

RL of base of dam = 1250.00m

RL of FRL 1280.00m

Height of wave 1.5m

Safe compressive strength 1200kN/m<sup>2</sup>

Specific gravity

Sketch the profile.

(08 Marks)

List the design criteria for earth dams.

(07 Marks)

Explain the steps in fixing the preliminary dimensions of an earth dam.

(08 Marks)

## PART - B

Design a surplus weir with stepped apron of a tank with the following details

Catchment area  $20 \text{km}^2$ 

Maximum water level 124.000m

Full tank level 123.000m

Ground level at weir site 122.000m

Shelow proposed weir upto a reach of 5m 121.000m 125.500m

Tank bund level

Top width of tank bund 2.0m

Side slopes of bund on either side 2H:1V

Hard foundation available at 120.000m

Ryve's coefficient 9

Hydraulic gradient 1:5

(25 Marks)



10CV65

Draw to a suitable scale:

Half plan at top and half plan at foundation.

(20 Marks) (15 Marks)

Half elevation and half sectional elevation.

Cross section across the weir.

(10 Marks)

Design details of a canal regulator is as follows: 5

d/s Particulars us  $13 \text{m}^3/\text{s}$  $16m^3/s$ Full supply discharge 10m 10m Bed width 12.000m 11.500m Full supply level 13.000m 12.500m Top level of Bank 10.000m 10.000m Canal bed level 2m 2mTop width of bank 2H:1V 2H:1V Canal side slopes

Bligh's coefficient = 10

General GL at the site = 12.00m

Good soil for foundation is at 9.000m

Design Ventway, Gates, Apron, and Protection works (25 Marks)

Draw to a suitable scale:

Half plan at top and half plan at foundation.

(20 Marks)

Half elevation and half sectional elevation.

(15 Marks)

Sectional elevation through regulator vent.

(10 Marks)